

ADDENDUM NO. 2

Date: March 23, 2023

PROSPECTOR PARK PROJECT

Bids to be received: **2:00 P.M., Thursday, March 30, 2023**

This Addendum is applicable to the work designated herein and shall be a part of and be included in the Contract. The Contractor shall acknowledge his/her acceptance of this addendum by initialing the line designated 'Acknowledge Addenda' at the end of the Sealed Proposal Form. All other provisions of the Project Manual shall remain in effect.

- Item #1. Change:** Change B/L2.3 note #2 to read: ASPHALT CONCRETE SURFACE COURSE: 3/8" NOMINAL MAX AGGREGATE SIZE, SEE SPECIFICATIONS.
- Item #2. Change:** Change B/L2.3 note #3 to read: ASPHALT CONCRETE BASE COURSE: 1/2" NOMINAL MAX AGGREGATE SIZE, SEE SPECIFICATIONS.
- Item #3. Change:** Change Specification Section 32 12 16, 2.01, B: Aggregate for Base Course Mix: Shall be 1/2" aggregate in accordance with Caltrans Standard Specifications, Section 39.
- Item #4. Change:** Change Section 32 12 16, 2.01, C: Aggregate for Surface Course Mix: Shall be 3/8" aggregate in accordance with Caltrans Standard Specifications, Section 39.
- Item #5. Clarification:** The Vehicular AC paving in the parking lot (2-01 on sheet L1.0) shall be installed in one (1) three-inch (3") lift, using 1/2" maximum aggregate size. The Basketball and Tennis Court Asphalt Paving (2-02 & 2-03 on sheet L1.0, and detail B on sheet L2.3) shall be installed in two (2) lifts. The lower (Base Course) shall be a 3-1/2" lift, using 1/2" maximum aggregate size. The upper (Surface Course) shall be a 1-1/2" lift, using 3/8" maximum aggregate size.
- Item #6. Clarification:** Delete Specification Section 32 12 16, 3.04 PREPARATION - PRIMER. No "primer" or "prime coat" will be required on the aggregate base for any asphalt paving areas.
- Item #7. Clarification:** Sheet L1.4, upper right/northeast corner of the park site – This "ramp" shown that references detail 1/C-13, shall only have the A1-6 curb installed on the uphill (north) side of the ramp/walk as indicated by the double line. In addition, this is not a "ramp" since it is less than 5%. The ramp detail is referenced to provide for the A1-6 curb on the uphill side of the walk.
- Item #8. Clarification:** Concrete Paving Spec Section 32 13 13 – 12 - The aggregate to be used for the exposed aggregate finish Section B shall be 3/8" "Lodi Brown" as available from Hasties Sand & Gravel (916) 361-2760.
- Item #9. Correction:** Concrete Paving Spec Section 32 13 13 – 3- and Detail B/L2.0 conflict in concrete requirements for walkways. The concrete type for

Prospector Park – Addendum #2

walkways and concrete paving shall be Class 'B' per Cal Trans Specs w/ min. 3,000 psi strength.

Item #9. Clarification: Detail B/L2.0 – the wire mesh shall be 10 gauge, 6" x 6" welded wire mesh.

This Addendum consists of 2 pages.

This concludes Addendum #2.